

SDMS US EPA Region V

Imagery Insert Form

Document ID:

177628

Some images in this document may be illegible or unavailable in SDMS. Please see reason(s) indicated below:

X

Illegible due to bad source documents. Image(s) in SDMS is equivalent to hard copy.

Specify Type of Document(s) / Comments:

TEXT TOWARD END OF EXHIBIT II

Includes _____ COLOR or _____ RESOLUTION variations.

Unless otherwise noted, these pages are available in monochrome. The source document page(s) is more legible than the images. The original document is available for viewing at the Superfund Records Center.

Specify Type of Document(s) / Comments:

Confidential Business Information (CBI).

This document contains highly sensitive information. Due to confidentiality, materials with such information are not available in SDMS. You may contact the EPA Superfund Records Manager if you wish to view this document.

Specify Type of Document(s) / Comments:

Unscannable Material:

Oversized _____ or _____ Format.

Due to certain scanning equipment capability limitations, the document page(s) is not available in SDMS. The original document is available for viewing at the Superfund Records center.

Specify Type of Document(s) / Comments:

Document is available at the EPA Region 5 Records Center.

Specify Type of Document(s) / Comments:

HEALTH AND SAFETY PROJECT SUMMARY
RAPID RESPONSE LEAD CONTAMINATION REMEDIATION
FOR NL INDUSTRIES/TARACORP SUPERFUND SITE
IN GRANITE CITY, VENICE, AND MADISON, ILLINOIS

Submitted to:

Department of the Army
Corps of Engineers
Omaha, Nebraska

Prepared by:

OHM Remediation Services Corp.

Gina Parchomenko
Industrial Hygienist
Midwest Region

Reviewed by:

Bill Thomas, CIH, CHP
Regional Health and Safety Manager
Midwest Region

September 3, 1993
Project # 13407

TABLE OF CONTENTS

- 1.0 INTRODUCTION
 - 2.0 PROJECT SUMMARY AND CONCLUSIONS
 - 3.0 SITE SAFETY AND HEALTH PLAN EVALUATION
 - 4.0 SITE SAFETY
 - 4.1 Accidents
 - 4.2 Preventive Measures
 - 5.0 EXPOSURE MONITORING
 - 5.1 Methodology
 - 5.1.1 Direct Reading
 - 5.1.2 Integrated
 - 5.1.3 Medical Monitoring
 - 5.2 Action Levels
 - 5.3 Sample Results
 - 5.3.1 MINIRAM Monitoring
 - 5.3.2 Personnel Monitoring
 - 5.3.3 Perimeter Monitoring
- EXHIBIT I: Amendment to Site Safety and Health Plan
EXHIBIT II: Air Monitoring Protocol
EXHIBIT III: Samples of Analytical and Logged Data
EXHIBIT IV: Location Maps

1.0 INTRODUCTION

- 2.1 Work for this project involved excavation and disposal of lead contaminated fill material placed in alleys, parking lots, driveways and yards in residential communities located in Granite City, Madison, and Venice, Illinois.
- 2.2 The NL Industries/Taracorp Plant is a former secondary lead smelting operation. Property adjacent to the plant was used to separate wastes for recycling. Lead contaminated battery casings were crushed and used as fill material in residential communities in and around Granite City, Illinois.

2.0 PROJECT SUMMARY AND CONCLUSIONS

2.1 SUMMARY

- 2.1.1 One amendment was made to the Site Safety and Health Plan (SSHP) to address changes made to the level of personal protection required. Refer to Exhibit I of this report for a copy of the amendment.
- 2.1.2 One OSHA recordable accident took place on-site. The accident did not result in any lost work time and appropriate provisions were made to prevent future incidents.
- 2.1.3 Task specific hazard evaluations were performed each day at each work site prior to the start of work.
- 2.1.4 Air monitoring data was used at this project to ensure that appropriate personal protection was being used for site conditions. Personnel medical monitoring was performed prior to and at the end of the project to determine lead levels in the blood.
- 2.1.5 MINIRAM data was used to determine when dust control measures should be implemented to prevent/control exposure as well as perimeter emissions. Data collected indicated 26 instances where the action level was exceeded; visual criteria was used to determine when to implement dust control.
- 2.1.6 Perimeter sampling data for total lead indicated 10 samples with concentrations above the detection limit. Visible dust emanating from the site perimeter was used as criteria for implementing dust control.
- 2.1.7 Personnel air sampling data indicated 13 detectable readings for total lead. Only four of those exceeded the action level of $15.0 \mu\text{g}/\text{m}^3$, set by the United States Army Corps of Engineers (USACE), all of which were recorded prior to 6/2/93; personnel were outfitted in Level C PPE and were therefore adequately protected for the lead levels registered. There were no recorded cases of personnel overexposure to ambient lead levels.

2.2 CONCLUSIONS

- 2.2.1 The SSHP was effectively implemented to address the health and safety hazards associated with each phase of site operations, and to meet the requirements set forth in 29 CFR 1910.120.
- 2.2.3 OHM Health and Safety Department concludes that the existing location-specific safety and health plan (SSHP) is appropriate for future phases of work at this site involving the same work activities.
- 2.2.3 Future work should be performed in Level D PPE with appropriate air monitoring to verify the selection of PPE. An action level of $30 \mu\text{g}/\text{m}^3$ should be used to warrant controls. Once monitoring shows consistent readings below the action level, the amount and frequency of air monitoring shall be appropriately limited/reduced.
- 2.2.4 Special attention should be paid to prevent any recordable accidents and near misses during the course of future work. Routine tasks should be reviewed and evaluated for potential hazards. Daily safety meetings should be implemented to prevent injuries on-site.

3.0 SITE SAFETY AND HEALTH PLAN EVALUATION

3.1 A location-specific safety and health plan was issued before the start of this project to address the health and safety hazards associated with each phase of site operations; the plan met the requirements of 29 CFR 1910.120.

3.2 The phases of work addressed in the SSHP include the following:

- Mobilization
- Installation of perimeter fence
- Bag and stockpile non-hazardous material*
- Soil sampling
- Excavation of contaminated soil
- Load-out of contaminated soil
- Backfill of excavation
- Restoration of disturbed areas
- Decontamination and demobilization

3.3 *Once on site, waste materials were designated to be direct loaded into dump trucks instead of being bagged.

3.4 Provisions were made to address heavy equipment, excavation and other physical hazards. Hazards associated with vehicle and pedestrian traffic in the work areas near roadways were controlled by the use of warning signs, men at work signs, and road guards to direct traffic. Personal protective equipment provisions were made to minimize exposure to lead contamination for personnel on-site, as well as to limit off-site emissions.

3.5 The minimum of Level C personal protection was required at the start of work on this project, to include the following:

- Full-face air purifying respirator with GMC-H cartridges
- Hard hat
- Polycoated Tyvek coveralls
- Steel toed boots
- Nylon booties (inner)
- Robar/Tingley boots (outer)
- Vinyl sample gloves (inner)
- Cloth, leather, or PVC gloves (outer)

- 3.6 An amendment was made to the SSHP for downgrading the level of personal protective equipment (PPE) from Level C to Level D for personnel working in the exclusion zone. This amendment was issued based on air monitoring data analysis showing non-detectable levels or levels of ambient lead contamination consistently below the action level for samples taken in the excavation areas. The amendment was issued by the site safety officer, under the direction of the Regional Health and Safety Manager, who is certified by the American Board of Industrial Hygiene. The amendment was approved June 2, 1993 by USACE Representative, Chuck Malin. Refer to Exhibit I for a copy of the amendment.
- 3.7 The downgrade of PPE made provisions for personnel to wear Level D PPE during site activities, to include the following protective equipment:
- Hard hat
 - Safety glasses
 - Steel toed leather safety shoes/boots
 - Polycoated Tyvek coveralls
 - Nylon booties (under) and Robars/Tingleys (outer)
 - Inner sample gloves - outer cloth or leather gloves
- 3.8 An action level of $15.0 \mu\text{g}/\text{m}^3$ of airborne lead, as determined by integrated sampling, was set by USACE to upgrade the level of PPE to Level C, including use of an air purifying respirator. Air monitoring was performed for the duration of remedial activities to ensure proper PPE use.

4.0 SITE SAFETY

4.1 Accidents

Employee safety during work on this project was OHM's first priority. During the course of this project, one OSHA recordable accident occurred, involving a cut to an employee's knuckle and finger while he was working on a metal fence post. The employee received stitches and was able to return to work without recording any lost work time. The accident was investigated and the potential hazard was brought to the attention of site personnel during a morning safety meeting the following day. The employees were instructed to use protective leather/cut resistant work gloves during activities involving sharp surfaces and tools and to protect sharp or dangerous work surfaces as feasible.

4.2 Preventive Measures

- 4.2.1 A number of measures were taken on-site to prevent accidents and injuries. Daily safety meetings were held to discuss hazards associated with upcoming work tasks, the use of specific tools and equipment, and other chemical, physical and environmental hazards associated with site work. Task specific hazard evaluations were performed each day at each work site prior to the start of work.

Controls were used to eliminate the hazards associated with vehicle and pedestrian traffic near the work locations. Warning signs were posted and guards were used to direct traffic.

- 4.2.2 A heat stress prevention program was instituted on-site. Personnel heat stress monitoring was performed to control the onset of heat related illnesses during work in high ambient temperatures. Employees' body weights were recorded at the start of the work shift and were rechecked at the end of the shift to determine any change in body weight potentially due to fluid loss.
- 4.2.3 Site workers' pulse, body temperature, and blood pressure were taken before and after each break. Work-rest schedules were determined by the results of this monitoring in accordance with the SSHP heat stress monitoring criteria.

- 4.2.4 Specific work-rest regimens were established at the start of every work day, based on the specific work conditions for that day (temperature, time of day, amount of sun or shade, etc.) Breaks were taken as designated throughout the work shift in shady areas, with personal protective equipment removed, cool liquids (juice, water) provided. Visual observation by a designated safety official was used to identify individuals exhibiting symptoms of heat related illness and to take the necessary action.

5.0 EXPOSURE MONITORING

Work for the Granite City project involved excavation of lead contaminated soil and battery casings at various sites throughout Granite City, Madison, and Venice, Illinois. The potential for exposure to these contaminants existed through dust migration in the air and personnel and equipment tracking.

5.1 Methodology

Air monitoring was performed to determine the ambient levels of total suspended particulates generated during excavation, and to determine total ambient lead exposure for site personnel and perimeter emissions. Wind direction at the start of each work day was used to determine the placement of sampling instruments on-site. Refer to Exhibit II for the air monitoring protocol used during site operations.

5.1.1 Direct Reading

Direct reading aerosol monitors (MINIRAM Aerosol Monitor, Model PDM-3 or equivalent) were used to determine levels of total suspended particulates (dust) at each excavation site.

The MINIRAM operates based on the detection of scattered electromagnetic radiation (light.) The MINIRAM requires no pump for its operation, and is designed to respond to particle sizes in the range of 0.1 to 10 μm (micrometers) It displays its results as mg/m^3 , and the measurement ranges are 0.01 to 10 mg/m^3 and 0.1 to 100 mg/m^3 , $\pm 0.02 \text{ mg}/\text{m}^3$ (1 minute averaging.) MINIRAMS were zeroed daily before each reading (approximately every 30 minutes) to ensure effective measurements.

MINIRAMS were used on-site to supplement visual observation in providing effective dust control. Three samples were taken approximately every 30 minutes during site operation; one sample was taken upwind of excavation operations and two were taken downwind. Results were recorded in a logbook kept on-site.

5.1.2 Integrated Sampling

Personnel and perimeter samples were taken to determine the levels of total lead in the air in the personal breathing zone and at the site perimeter. Lead samples were collected and analyzed using NIOSH method 7082, using battery

operated air sampling pumps (Gillian or equivalent) fitted with 37 mm mixed cellulose ester (MCE) filters, 0.8 micron pore diameter.

5.1.2.1 Perimeter Sampling

Three perimeter samples were taken daily over the course of the work shift. One sample was taken upwind of site operations and two were taken downwind. Perimeter samples were taken above ground level (approximately 4-5 feet in height) to characterize the breathing zone and to prevent contamination due to foot traffic. The pump flowrate was calibrated and set at about 10 liters per minute for the duration of the task (approximately 8 hours.)

Pumps were calibrated using a secondary standard, a rotameter, to determine the sample flowrate. Calibration readings and sample results were documented in project logbooks kept on-site. Analytical and calibration data are available in the OHM Findlay, Ohio office. Refer to Exhibit III for samples of this data.

5.1.2.2 Personnel Sampling

Personnel air samples for lead were taken for a representative number of employees performing intrusive activities within the exclusion zone (one employee from each job category - at least two employees per day.) The samples were taken in the person's breathing zone for the duration of the shift worked on that day.

Samples were collected at the end of the work day and sent to the analytical lab for analysis for total lead. A blank sample was included in the shipment.

Samples were assigned identification numbers based on an established code. Refer to Exhibit II, section 4.3, for a copy of the code.

The analytical laboratory used was Chemtex, 3082 25th Street, Port Arthur, Texas. Standard turnaround for sample results was 24 hours by facsimile; original data was mailed.

Direct reading (MINIRAM) and integrated (perimeter) samples were taken in approximately the same locations (within 3 feet) at the work sites. Maps depicting a typical air monitoring set-up for each excavation site are presented in Exhibit IV of this report, detailing the location of real-time monitors and perimeter pumps.

5.1.3 Medical Monitoring

Personnel blood lead levels were determined prior to and after the completion of work for this project. Monitoring was performed in accordance with the requirements of 29 CFR 1910.1025 for personnel working in contaminated areas.

5.2 Action Levels

Action levels were determined for use with the MINIRAM by taking a predetermined average, provided by USACE, and adding it to the background reading taken at the start of the work shift.

The action level was used to determine when dust control measures should be implemented. If the action level was exceeded during the course of work, and was believed to be caused by site activities (i.e. downwind of excavation), operations would cease and wet spray control measures would be implemented to reduce/eliminate dust emissions. Work in the work zone resumed once visible emissions were controlled and readings dropped to below the action level.

During lead excavation operations for this project, the specified action levels for the MINIRAM and personnel monitoring were exceeded 26 and 4 times respectively, primarily at the Missouri Avenue site. The majority of these readings were results of upwind samples, attributed to area vehicle traffic rather than site operations.

5.3 Sample Results

5.3.1 MINIRAM Monitoring

Readings were taken daily on-site, approximately every 30 minutes, using the MINIRAM; one upwind and two downwind of excavation/intrusive activities.

The total dust levels detected by the MINIRAM over the course of this project ranged from Non-detectable ($ND < 0.01 \text{ mg/m}^3$) which reads 0.00 on the monitor, to about 4.0 mg/m^3 of total dust. The majority of these readings did not exceed their location specific action levels, and did not exceed the ACGIH TLV of 10 mg/m^3 . The readings were used in conjunction with visible dust levels to indicate when dust control measures were needed (wet spray.)

The following is a listing of some of the instances in which the action levels for total dust were exceeded and the surrounding circumstances:

Table 5.3-1
MINIRAM READINGS ABOVE THE ACTION LEVEL (AL)

NUMBER > AL (mg/m ³)	AL (mg/m ³)	LOCATION	DATE	OPERATIONS PERFORMED
1 @ .23 1 @ .21	0.17	Missouri Av (downwind)	4/15/93	Loading truck, excavating
1 @ .18 1 @ .23 1 @ .15	0.14	Missouri Av (upwind)	4/16/93	Excavating, loading, clearing fence line
3 @ 1.46 8 @ 2.09 3 @ 2.10	0.25	Missouri Av (upwind)	4/21/93	Excavating, loading trucks
1 @ 2.5	2.49	Missouri Av (upwind)	4/28/93	Soil loadout
1 @ 2.54	2.53	Missouri Av (upwind)	4/29/93	Excavating
2 @ 2.53 2 @ 2.63 1 @ 2.83	2.51	Missouri Av (upwind)	5/6/93	Excavating

The upwind total dust levels detected by the MINIRAM were higher than the downwind levels consistently over the course of work on this project.

5.3.2 Personnel Monitoring

Personnel performing intrusive activities such as operating or spotting an excavator, stockpiling operations, hand excavating, loading soils, etc. were sampled for total airborne lead exposure. Samples were taken in the individual's breathing zone, using Gillian sampling pumps equipped with 37 mm cassettes. NIOSH method 7082 was used for sampling and analysis.

The majority of samples analyzed showed non-detectable levels* of lead. Detectable lead levels were found under the following circumstances as listed:

Table 5.3-1
PERSONNEL LEAD MONITORING RESULTS

DATE	LEVEL (mg/m ³)	LOCATION	ACTIVITY
4/23/93	0.00021	Missouri Ave	Guiding/lining trucks
4/27/93	0.4120	Missouri Ave	Guiding/lining trucks; hand excavating
5/13/93	0.0510	Missouri Ave	Hand excavating
5/17/93	0.1320	Terry St	Spotting, placing bows on trucks
5/18/93	0.009	Hill	Hand excavating
	0.0610	Hill	Hand excavating
	0.0020	Harrison	Spotter
5/19/93	0.0100	Harrison	Spotter, erecting bows
6/7/93	0.0021	Terry St	Hand excavating
6/18/93	0.0056	Cleveland	Hand excavating; spotter
6/25/93	0.0021	Delmar	Truck loading
6/29/93	0.0015	Terry St	Excavator operator
6/30/93	0.0014	Cleveland	Operator

*Non-detectable levels ranged from <0.0002 to <0.0025 mg/m³

Until the addendum to the HASP was made (6/2/93), site personnel working in the exclusion zone wore MSA full face air purifying respirators with GMC-H cartridges at all times.

As is evident in the personnel monitoring data, the highest detectable level of lead was 0.4120 mg/m³ 8-hour TWA. This individual as well as the majority of

personnel with detectable exposure levels of lead over the AL were performing very close, intrusive operations such as hand excavating lead contaminated soils. Other personnel were spotting excavator operations, which put them in close proximity to the dusts generated during excavation. As all of these readings (>AL) were logged before 6/2/93, personnel were outfitted in Level C PPE including an air purifying respirator at all times during the course of work. There were no readings over the action level after 6/2/93, and therefore the level of protection (Level D) was appropriate for work being performed.

5.3.3 Perimeter Monitoring

Perimeter sampling for lead levels emanating from the site was conducted using the same sampling and analytical method as the personnel sampling; however the pumps were mounted and positioned around the perimeter of the site (1 upwind and 2 downwind), in approximately the same locations as the MINIRAMS.

Perimeter sample results indicated predominantly non-detectable lead levels*. The following list presents detectable lead levels and the surrounding circumstances:

Table 5.3-2
PERIMETER MONITORING RESULTS

DATE	LOCATION	READING (mg/m ³)	ACTIVITY
5/17/93	Terry	0.0005 (upwind)	Stocking and loading trucks
		0.0017 (downwind)	Stocking and loading trucks
6/4/93	Weber	0.00095 (upwind)	Loading trucks
6/7/93	Terry	0.00195 (upwind)	Excavating
6/9/93	Missouri Av	0.0038 (upwind)	Loading trucks
6/15/93	Colgate	0.0006 (upwind)	Excavating
6/16/93	Cleveland	0.0022 (upwind)	Excavating
6/23/93	Delmar	0.0004 (upwind)	Excavating
6/28/93	Delmar	0.0009 (upwind)	Excavating
6/29/93	Terry	0.0009 (upwind)	Excavating

* Non-detectable levels ranged from <0.00025 to <0.002 mg/m³

EXHIBIT I
AMENDMENT TO SITE SAFETY AND HEALTH PLAN

AMMENDMENT TO SAFETY AND HEALTH PLAN
RAPID RESPONSE LEAD CONTAMINATION REMEDIATION

The following changes will be made in the levels of protection to be worn during excavation and load-out of contaminated soil operations as written in section 6.3 Task Specific Protection Level of the Site Safety Plan.

Modified Level D will be permitted during excavating/loading activities in the exclusion zone due to our successful use of engineering controls (wetting techniques) and the supporting analytical results of non-detectable lead in air concentrations obtained through personal and perimeter air monitoring.

Modified Level D will be as follows:

- Hard Hat
- Safety Glasses
- Steel Toed Leather Safety Shoes or Boots
- Polycoated Tyvek
- Nylon Booties (inner) - Robars or Tingles (outer)
- Inner Sample Gloves - Outer Cloth or Leather Gloves

Chuck Malin of the USACE has reviewed the supporting analytical data and the conditions on which the downgrade has been set. Downgrade was approved June 2, 1993 at 1430 by USACE Representative, Chuck Malin.

EXHIBIT II
AIR MONITORING PROTOCOL

PROTOCOL FOR AIR MONITORING
RAPID RESPONSE LEAD CONTAMINATION REMEDIATION

1 Purpose

- 1.1 The purpose of this protocol is to document the methods used to perform air monitoring at the Lead Remediation Project in Granite City, Illinois.
- 1.2 The monitoring is intended to meet the requirements of the OSHA standard for personnel exposure to lead, 29 CFR 1910.1025.

2 Scope

- 2.1 Air monitoring for total airborne dust is performed using a direct reading instrument, equivalent to MIE Miniram Aerosol Monitor, Model PDM-3.
- 2.2 Monitoring for airborne lead in the personnel breathing zone is performed using a battery operated sampling pump worn during the workshift.
- 2.3 Monitoring for airborne lead at the perimeter of the exclusion zone is performed using an electrically powered pump, operated for the duration of the work during the day.

3 Operating Protocol

3.1 Direct Reading Instruments

- 3.1.1 Each instrument is designed to measure total dust. An action level has been established for each individual project site.
 - 3.1.1.1 The action levels are documented in section 9.7 of the Safety and Health Plan.
 - 3.1.1.2 The allowable concentration for a particular site was established according to the concentration of lead found in the soil at the site.

- 3.1.2 Direct reading instruments are placed on a tripod and located at the perimeter of the exclusion zone.
- 3.1.3 Two monitors are located downwind, one instrument is located upwind.
- 3.1.4 Instruments are calibrated by the factory, at least every twelve months.

3.2 Personnel Air Samples

- 3.2.1 Air samples are collected to measure total lead in the personnel breathing zone. The procedures for collection and analysis are equivalent to the procedure, NIOSH 7082.
- 3.2.2 A mixed cellulose ester filter, 0.8 micron pore diameter, is used to collect the sample. The pump flowrate is calibrated and is set at 2 liters per minute (L/min).
- 3.2.3 The pump is operated for the duration of the task and terminated at the end of the shift.
- 3.2.4 The pump is attached to the technician with the filter cassette located in the breathing zone. The pump is placed inside the disposable coveralls.
- 3.2.5 At least two samples are collected each day for two different people.
- 3.2.6 The air flowrate is measured using a primary calibration standard, equivalent to a Gillibrator. The flowrate, measured in the afternoon, is recorded on a log sheet and is used as the beginning flowrate for the next day. The battery for the pump is charged overnight.

3.3 Perimeter Air Samples

- 3.3.1 Air samples are collected to measure total lead at the perimeter of the exclusion zone. The procedures for sample analysis are equivalent to the procedure. NIOSH 7082.

- 3.3.2 A mixed cellulose ester filter, 0.8 micron pore diameter, is used to collect the sample. The pump flowrate is calibrated and is set at approximately 10 liters per minute (L/min).
- 3.3.3 The pump is operated for the duration of the task and terminated at the end of the shift.
- 3.3.4 The filter cassette is attached to a tripod at approximately 5 feet from the ground and located at the perimeter of the exclusion zone.
- 3.3.5 Two monitors are located downwind. one instrument is located upwind, near the direct reading instruments.
- 3.3.6 Instruments are calibrated by the factory, at least every twelve months.
- 3.3.7 The air flowrate is measured using a secondary calibration standard. Specifically, the rotameter is used to estimate the sample flowrate. The flowrate is measured in the afternoon is recorded on a log sheet and is used as the beginning flowrate for the next day. The battery for the pump is charged overnight.

4 Sample Analysis

- 4.1 The samples are retrieved at the end of the day and sent to the analytical lab for analysis of total lead. A blank is included in the shipment.
- 4.2 Results for samples are listed in a project logbook. The activities performed during the day are listed in the sampling log book.

4.3 The sample number is selected using the following code:

- XXX Abbreviation for the site or.
PER for a personnel sample.
- 00 Sequential sample number for the day of collection.
- XX Abbreviation for person who collected the sample or the initials of the person who wore the personnel pump.
- 000 Sequential Workday number or the month and day when the sample was collected.

4.3.1 The sample number for an area sample collected on April 14, 1993 at the Missouri Avenue site by Mark Proctor is MISUIMP01.

4.3.2 The sample number for a personnel sample collected on April 14, 1993 for John Hester is PERUJH414.

EXHIBIT III
SAMPLES OF ANALYTICAL AND LOGGED DATA

MINIRAM LOG

BG 2.90
PDL .93
HL 3.83

6-9-93 Sunny WINDS Temp 82° Hum 72%

0500 Command lost prepare for today

0600 Safety meeting M Sakuma general

0630 H8607 st set up zone, set pumps

Manuel FM

R Thas OP

Gilman pump 9656 0730

J Kennedy RT

R Surri RT

R Dandridge RT

J Beahley RT

R Fieels RT

0645 2 special waste trucks loaded

out of Weber. Hic horn tested & heard by crew.

0730 Crew on H8607 ST Bellman on site

1 st truck being loaded out of H8607

J Beahley, J Kennedy Weber Beckill ground

compacting. Concrete sub contractor starting

to set forms on Weber West

Mini Ram S/N High Vol Pumps S/N

#1 5357

#1 3296

#2 5428

#2 3295

#3 4378

#3 2534

8900 Crew out of zone

0945 Crew load Bellman 1 st 2 trucks light

Cunningham 2 trucks on site Weber, Abbott

for special waste.

1.1.24.1

Mayor of Venice on site.

1215 M. Janet lead two special weeks Cannington

Trucks Weber west.

~~1300~~ Lunch

1345 Water truck waiting down Abbott St. East

Weber's concrete crew pouring slab.

1605 OFF site

1715 END OF DAY

Min. Rain ABBOTT ST 6/9/85

0800 1 2.90 1630 1 2.91 1300 1 2.92 1530 1 2.85

2 1.88 2 1.86 2 1.35 2 1.85

3 .18 3 .19 3 .15 3 .15

0830 1 2.90 1100 1 2.90 1330 1 2.91 1600 1 2.85

2 1.86 2 1.85 2 1.86 2 1.85

3 .18 3 .17 3 .15 3 .19

0900 1 2.91 1130 1 2.90 1400 1 2.92

2 1.86 2 1.84 2 1.85

3 .19 3 .15 3 .15

0930 1 2.91 1200 1 2.89 1430 1 2.92


2 1.87 2 1.82 2 1.86

3 .18 3 .16 3 .16

1000 1 2.92 1230 1 2.85 1500 1 2.91

2 1.86 2 1.80 2 1.86

3 .19 3 .15 3 .16



(

Job No.: 13407

Operator: J. DeHouwe

Calibration: _____

AML Component, Date

Sampling Technique: #1 = Upwind #2 & 3 = Downwind

208 Terry st

Sample Interval: 30 min

Background Reading: .90 mg/L² Predetermined Avg = .09 mg/L²

Action Level/Response: 99 mg/L³

[illegible]



OHM Corporation

PERSONAL SAMPLING DATA SHEET

PROJECT # 13407

DATE: APRIL 15 1993

PERFORMED BY: MARK S. PRATOR

DAY: THURSDAY

TITLE: Health + Safety

SAMPLE NO.	NAME	TASK PERFORMED	ANALYSIS METHOD	37mm CTS ₁	FLOW RATE (L/MIN)			TIME		TOTAL TIME(MIN)
				SAMPLING MEDIA	PRE	POST	TOTAL VOL(L)	START	STOP	
PER 053W 415	John Wysock #5371	Lining trucks w/ viqueen	Lead	Pump #9636	2.00 l/m	2.00 l/m	960	0900	1700	480 min
PER 063H 415	John Hester #1834	Operating Excavator	Lead	Pump #6071	2.00 l/m	2.00 l/m	960	0900	1700	480 min
	Did NOT	USE TODAY		Pump #9892	2.00 l/m	2.00 l/m				
PER 07 BS 415	_____	_____	Lead	Blank	_____	_____	_____	_____	_____	_____

REMARKS:



OHM Corporation

PERSONAL SAMPLING DATA SHEET

PROJECT # 13407

DATE: APRIL 14, 1993

PERFORMED BY: MARK S. PROCTOR

DAY: WEDNESDAY

TITLE: HEALTH & SAFETY

SAMPLE NO.	NAME	TASK PERFORMED	ANALYSIS METHOD	37mm MCE SAMPLING MEDIA	FLOW RATE (L/MIN)		TOTAL VOL.(L)	TIME		TOTAL TIME(MIN)
					PRE	POST		START	STOP	
PER02 RF 414	K. Foggy #5471	DIGGING WITH SHOVEL LOCATING UTILITY LINES	LEAD	Pump# 6071	2.02 l/m	2.00 l/m	960 (L) TOT. VOL.	0900	1700	480 min
PER03 JW 414	J. Wysock #5371	DIGGING WITH SHOVEL LOCATING UTILITY LINES	LEAD	Pump# 8749	2.01 l/m	2.00 l/m	960 (L) TOT. VOL.	0900	1700	480 min
				Pump# 9890	2.01 l/m					
PER01 JH 414	J. Hester #1934	OPERATING EXCAVATOR	LEAD	Pump# 7171	2.04 l/m	2.04 l/m	600 (L) TOT. VOL.	1230	1730	300 min
				Pump# 9892	2.00 l/m					
				Pump# 11021	2.00 l/m					
				Pump# 4424	2.05 l/m					
PER04 BS 414	_____	_____	LEAD	BLANK	_____	_____	_____	_____	_____	_____

REMARKS:

APRIL 22, 1993

18501100 20/1/93

SAMPLE NO.: PER 24 JH 422
LOCATION: MISSOURI AVE
EMPLOYEE: JOHN HESTER
ACTIVITY: EXCAVATING & MOVING SOILS / CAT 215
EXPOSURE TIME: 540 MIN
SAMPLE RESULTS: $< 0.00020 \text{ mg/m}^3$
REPORT DATE: 4/26/93
PERFORMED BY: CHEMTEX LAB 3041601

SAMPLE NO.: PER 25 DK 422
LOCATION: MISSOURI AVE.
EMPLOYEE: DWIGHT KILGORE
ACTIVITY: GUIDING AND LINING TRUCKS
EXPOSURE TIME: 540 MIN
SAMPLE RESULTS: 0.00021 mg/m^3
REPORT DATE: 4/26/93
PERFORMED BY: CHEMTEX LAB 3041602

SAMPLE NO.: PER 26 BS 422
LOCATION: MISSOURI AVE.
EMPLOYEE: "BLANK SAMPLE"
ACTIVITY: N/A
EXPOSURE TIME: N/A
SAMPLE RESULTS: $< 0.00125 \text{ mg/m}^3$
REPORT DATE: 4/26/93
PERFORMED BY: CHEMTEX LAB 3041603

NOTE: AT ALL TIMES WHILE EMPLOYEES WERE IN
THE EXCLUSION ZONE, M&A FULL FACE RESPIRATORS
WITH GMC-H CARTRIDGES WERE WORN. SAMPLES
WERE COLLECTED IN THE BREATHING ZONE.

2E IN
RATORS
SAMPLES

APRIL 23, 1993

SAMPLE No.: PER 27 JH 423

LOCATION: MISSOURI AVE.

EMPLOYEE: JOHN HESTER

ACTIVITY: EXCAVATING ; MOVING SOILS /CAT 215

EXPOSURE TIME: 480 MIN.

SAMPLE RESULTS: $< 0.00020 \text{ mg/m}^3$

REPORT DATE: 4/26/93

PERFORMED BY: CHEMTEX 3041608

SAMPLE No.: PER 28 DK 423

LOCATION: MISSOURI AVE.

EMPLOYEE: DWIGHT KILGORE

ACTIVITY: GUIDING AND LINING TRUCKS, HAND EXCAVATING

EXPOSURE TIME: 480 MIN

SAMPLE RESULTS: $< 0.00020 \text{ mg/m}^3$

REPORT DATE: 4/26/93

PERFORMED BY: CHEMTEX LAB 3041609

SAMPLE No.: PER 29 BS 423

LOCATION: MISSOURI AVE

EMPLOYEE: "BLANK SAMPLE"

ACTIVITY: N/A

EXPOSURE TIME: N/A

SAMPLE RESULTS: $< 0.00125 \text{ mg/m}^3$

REPORT DATE: 4/26/93

PERFORMED BY: CHEMTEX LAB 3041610

NOTE: AT ALL TIMES WHILE EMPLOYEES WERE IN THE EXCLUSION ZONE, MSA FULL FACE RESPIRATOR WITH GMC-H CARTRIDGES WERE WORN. SAMPLES WERE COLLECTED IN THE BREATHING ZONE.

May 8, 1993

SAMPLE NO.: M15015D07
LOCATION: MISSOURI AVE (UPWIND)
ACTIVITY: EXCAVATING, STOCKING, & LOADING SOILS
SAMPLE TIME: 390 MIN.
RESULTS: $7.0.00075 \text{ mg/m}^3$
REPORT DATE: 5/11/93
PERFORMED BY: CHEMTEX LAB 3050570

SAMPLE NO.: M15025D17
LOCATION: MISSOURI AVE (DOWN WIND)
ACTIVITY: EXCAVATING, STOCKING, & LOADING SOILS.
SAMPLE TIME: 390 MIN.
RESULTS: $7.0.00075 \text{ mg/m}^3$
REPORT DATE: 5/11/93
PERFORMED BY: CHEMTEX LAB 3050578

SAMPLE NO.: M15035D17
LOCATION: MISSOURI AVE (DOWN WIND)
ACTIVITY: EXCAVATING, STOCKING, & LOADING SOILS
SAMPLE TIME: 390 MIN.
RESULTS: $7.0.00075 \text{ mg/m}^3$
REPORT DATE: 5/11/93
PERFORMED BY: CHEMTEX LAB 3050572

SAMPLE NO.: M1504 ~~550~~ 17
LOCATION: MISSOURI AVE. ("BLANK SAMPLE")
RESULTS: $7.0.00125 \text{ mg/m}^3$
REPORT DATE: 5/11/93

PERFORMED BY: CHEMTEX LAB 3050573
NOTE: WIND: EAST TEMP: HI 85°F LOW 67°F
HUM: 62% SUNNY CLEAR

MAY 7 1993

Environmental Sampling

SAMPLE NO.: MIS01JD16
LOCATION: MISSOURI AVE (UPWIND)
ACTIVITY: EXCAVATING, STOCKING, & LOADING SOILS.
SAMPLE TIME: 240 MIN.
RESULTS: $< 0.00050 \text{ mg/m}^3$
REPORT DATE: 5/11/93
PERFORMED BY: CHEMTEX LAB 3050565

SAMPLE NO.: MIS02JD16
LOCATION: MISSOURI AVE. (DOWN WIND)
ACTIVITY: EXCAVATING, STOCKING, & LOADING SOILS.
SAMPLE TIME: 240 MIN.
RESULTS: $< 0.00050 \text{ mg/m}^3$
REPORT DATE: 5/11/93
PERFORMED BY: CHEMTEX LAB 3050566

SAMPLE NO.: MIS03JD16
LOCATION: MISSOURI AVE. (DOWN WIND)
ACTIVITY: EXCAVATING, STOCKING, & LOADING SOILS.
SAMPLE TIME: 240 MIN.
RESULTS: $< 0.00050 \text{ mg/m}^3$
REPORT DATE: 5/11/93
PERFORMED BY: CHEMTEX LAB 3050567

SAMPLE NO.: MIS04JD16
LOCATION: MISSOURI AVE. ("BLANK SAMPLE")
RESULTS: $< 0.00125 \text{ mg/m}^3$
REPORT DATE: 5/11/93
PERFORMED BY: CHEMTEX LAB 3050568

NOTE: WIND: SOUTHEAST TEMP: HI 85°F LOW 65°F
HUM: 69% SUNNY CLEAR

Environmental & Industrial Hygiene Services

Client: O H M Corporation
370 Old Rock Rd.
Granite City, IL 62040

Attn: Mr. Mark Sackman

Report Date: 6/17/93
Sample Source: Filters
Date Collected: 6/16/93
Collected By: Client
Date Received: 6/17/93
CHEMTEX FILE #: 3061312

PROJECT: 13407, U.S. ARMY CORP OF ENGINEERS, GRANITE CITY, ILLINOIS


RESULTS OF ANALYSIS

CHEMTEX #	Sample Identification	Lead (mg/m ³)
3061312	CLG01MS02	< 0.00035
3061313	CLG02MS02	< 0.00035
3061314	CLG03MS02	< 0.00035
3061315	CLG04MS02	< 0.00125 mg/Filter
3061316	PER136RT616	< 0.0020
3061317	PER138BS616	< 0.00125 mg/Filter

Date Analyzed/
Analyst

6/17/93
KR/DT

Analyzed by NIOSH Method 7082.



Dr. C. N. Reddy, Ph.D
Director

CMM/CNR



OHM Corporation

AIN-OF-CUSTODY RECORD

Form 0019
Field Technical Services
Rev. 08/89

No. 94460

O.H. MATERIALS CORP. • P.O. BOX 551 • FINDLAY, OH 45839-0551 • 419-423-3526

PROJECT NAME		PROJECT LOCATION		NUMBER OF CONTAINERS		ANALYSIS DESIRED (INDICATE SEPARATE CONTAINERS)										REMARKS		
PROJECT NO.		PROJECT CONTACT				PROJECT TELEPHONE NO.		<div style="display: flex; justify-content: space-around;"> <div>LEAD</div> <div>LEAD</div> <div>LEAD</div> <div>LEAD</div> <div>LEAD</div> <div>LEAD</div> </div>										
CLIENT'S REPRESENTATIVE		PROJECT MANAGER/SUPERVISOR																
ITEM NO.	SAMPLE NUMBER	DATE	TIME	COMP	GRAB	SAMPLE DESCRIPTION (INCLUDE MATRIX AND POINT OF SAMPLE)												
1	EL601MS02	4/4/93	3:00 PM			Flow AL Vol 3600 L CALGATE EXCAVATION - CONCRETE										1		
2	EL602MS02					Flow AL Vol 3600 L CALGATE EXCAVATION - CONCRETE										1		
3	EL603MS02					Flow AL Vol 3600 L CALGATE EXCAVATION - CONCRETE										1		
4	EL604MS02					Blank										1		
5	REL136TMB		3:00 PM			Flow AL Vol 7200 L CALGATE EXCAVATION - CONCRETE										1		
6	REL138B5MB	4/4/93				Blank										1		
7																		
8																		
9																		
10																		

TRANSFER NUMBER	ITEM NUMBER	TRANSFERS RELINQUISHED BY	TRANSFERS ACCEPTED BY	DATE	TIME	REMARKS
1	6	Mack Sablan	<i>[Signature]</i>	4/4/93		24 hr - final results - results in mg/l Fax to (619)-876-8406. Then Follow with Head Gg Data And to: OHM Corp 370 Old Rock Rd Granite City, Ill 62040
2						
3						
4						

SAMPLER'S SIGNATURE *[Signature]*

LAB COPY

TEL: 1-409-982-1522

CHEMTEX

JUN 17 '93 05:56 PM
J 1 409 982 1522 No. 015 P.

CHEMTEX

3082 25th Street Port Arthur Texas 77642 409-980-4575
FAX 409-980-1502

Environmental & Industrial Hygiene Services

Client: O H M Corporation
370 Old Rock Rd.
Granite City, IL 62040

Attn: Mr. Mark Sackman

Report Date: 6/16/93
Sample Source: Filters
Date Collected: 6/15/93
Collected By: Client
Date Received: 6/16/93
CHEMTEX FILE #: 3061219

PROJECT: 13407, U.S. ARMY CORP OF ENGINEERS, GRANITE CITY, ILLINOIS

RESULTS OF ANALYSIS

CHEMTEX #	Sample Identification	Lead (mg/m ³)
3061219	CVR01JD01	< 0.00055
3061220	CVR02JD01	< 0.00055
3061221	CVR03JD01	< 0.00055
3061222	CVR04BS01	< 0.00125 mg/Filter-

Date Analyzed/
Analyst

6/16/93
KR/DT

Analyzed by NIOSH Method 7082.



Dr. C. N. Reddy, Ph.D
Director

JLP/CNR

AIHA Accredited

Air Analysis • Biological Analysis
Industrial Hygiene Analysis • Organic Analysis • Petroleum Analysis
Plant Analysis • Soil Testing • Water Analysis

NIHAP Accredited



OHM Corporation

CHAIN-OF-CUSTODY RECORD

Form 0019
Field Technical Services
Rev. 08/89

No. 94462

O.H. MATERIALS CORP. • P.O. BOX 551 • FINDLAY, OH 45839-0551 • 419-423-3526

PROJECT NAME		PROJECT LOCATION		NUMBER OF CONTAINERS	ANALYSIS DESIRED (INDICATE SEPARATE CONTAINERS)	REMARKS
U.S. Army Corp. of Engineers		Granite City, IL				
PROJ. NO.	PROJECT CONTACT	PROJECT TELEPHONE NO.				
13407	Mark Sackman	(618) 876-9553				
CLIENT'S REPRESENTATIVE		PROJECT MANAGER/SUPERVISOR				
Chuck Malin		Dave Strickland				
ITEM NO.	SAMPLE NUMBER	DATE	TIME	COMP	GRAB	SAMPLE DESCRIPTION (INCLUDE MATRIX AND POINT OF SAMPLE)
1	KVR01J001	6/15/93	2:00 PM	X		37mm cassette (up wind Carver st)
2	KVR01J001	6/15/93	2:00 PM	X		37mm cassette (Down wind Carver st)
3	KVR03J001	6/15/93	2:00 PM	X		37mm cassette (Down wind Carver st)
4	KVR04B501	6/15/93	-	X		37mm cassette (Carver st)
5						
6						
7						
8						
9						
10						

TRANSFER NUMBER	ITEM NUMBER	TRANSFERS RELINQUISHED BY	TRANSFERS ACCEPTED BY	DATE	TIME	REMARKS
1		<i>[Signature]</i>	<i>[Signature]</i>	6/15/93	1700	24 hr Turn around results in mg/m^3 fax to (618) 876-8406. Then follow with reg. mail Hard. Copy Data To: OHM Corp 370 Old Rock Rd Granite City, IL 62040
2				6/16/93	1030 AM	
3						
4						

SAMPLER'S SIGNATURE

JUN 16 '93 04:39P

TEL: 1-409-982-1522

CHEMTEX

**EXHIBIT IV
LOCATION MAPS**

June 10, 1993 High Volume Pump Locations WIND S Temp 90° Hum 75%

LEGEND

SURFACE LOCATIONS OF BATTERY CASING MATERIAL
(PORTION OF AREA ESTIMATED HAS NOT BEEN SURVEYED)



>50% SURFACE COVERAGE



<50% SURFACE COVERAGE



TRACE

HAMPDEN AVENUE

SECOND STREET

THIRD STREET

Zach Moss
5469

HOUSE

#2

#3

VED003
+10.60

#1

VED004
+10.38

SHINGLED
GARAGE

UTILITY POLE (TYP.)


VED007
+13.06

VED006
+08.67

VED005
+08.70

ABBOTT STREET

DRAFT



⊗ High Volume Pumps Locations

High Volume Pumps S/N #1 3296
#2 3295

ML/TARACORP SUPERFUND SITE
GRANITE CITY, ILLINOIS
PRE-DESIGN FIELD INVESTIGATION

PROJECT NO
89MC114V

Woodward-Clyde
Consultants

DRN. BY: CU 7/14/82
DSGN. BY:
CHKD. BY:

REMOTE FILL AREAS.
VENICE ALLEYS (ABBOTT ST.)
? OF 5

7

File name: G:\CRASH\AIRMO11.DWG. Last edited: 82/08/11 @ 15:04

June 10, 1993

Mini Rem Locations for Site Activities

Wind S

Temp 90°

Hum 75%

Back Ground 2.80
Predetermined AVG .93
3.73

LEGEND

SURFACE LOCATIONS OF BATTERY CASING MATERIAL
(SECTION OF AREA ESTIMATED AND NOT BEEN SURVEYED)



>50% SURFACE COVERAGE



<50% SURFACE COVERAGE





TRACE

HAMPDEN AVENUE

SECOND STREET


THIRD STREET

Wind dir S
(0630 - 1330)



ABBOTT STREET

DRAFT



Mini Rem Locations




NL/TARACORP SUPERFUND SITE, GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO 89MC-14V
Woodward-Clyde Consultants		
DATE: BY: CU 7/14/92 DESIGN BY: CHECK BY:	REMOTE FILL AREAS: VENICE ALLEYS (ABBOTT ST.) 2 OF 3	PC NO 7

Mini Rem S/N #1 5397
#2 5428

June 7, 1993 Mini Ram Locations for Site Activities Winds W Temp 87° Hum 67%

LEGEND

SURFACE LOCATIONS OF BATTERY CASING MATERIAL
SHOWN BY AREA COVERAGE AND NOT BY DIMENSIONS

-  >50% SURFACE COVERAGE
-  <50% SURFACE COVERAGE
-  TRACE

SECOND STREET

WEBER STREET

THIRD STREET

VE0011 412.17
 CONC. PAD
 VE0016 413.15
 GARAGE

Back Ground 2.86
 Predetermined Avg 0.14
 Action Level 3.00
 Bar today

Zack Moss
 5469

#12
 VE0008 409.37
 VE0008 409.19
 APPROXIMATE W/OUT
 PERMANENT MONUMENTS

Wind direction SW
 0800 - 1600

DRAFT

0 50 100
 FEET
 SCALE

IN/TARACORP SUPERFUND SITE
 GRANITE CITY, ILLINOIS
 PRE-DESIGN FIELD INVESTIGATION

Woodward-Clyde
 Consultants

DATE: 7/14/92
 DRAWN BY: VENCE ALLEN (WEBER ST)
 CHECK BY: J. OF 5




PROJECT NO
 89UC114V


Mini Ram Locations for Site Activities
 Mini Ram s/n #1 5397

June 7/1993 High Volume Pump Locations Wind SW Temp 89° Hum 67%

LEGEND


SURFACE LOCATIONS OF BATTERY CASING MATERIAL
(NOTED BY DATA EXTRACTOR, AND NOT FIELD SURVEY)

-  >50% SURFACE COVERAGE
-  <50% SURFACE COVERAGE
-  TRACE



High Volume Pump Locations

High Volume Pump S/N #1 3296



DRAFT




MR./TARACORP SUPERFUND SITE
GRANITE CITY, ILLINOIS
PRE-DESIGN FIELD INVESTIGATION


Woodward-Clyde
Consultants

DATE: 7/14/92
PROJECT NO: 8900114V
REMOVAL FILL AREAS:
VEHICLE ALLEYS (WEBER ST)
3 OF 5

LEGEND

SURFACE LOCATIONS OF BATTERY CASING MATERIAL
(BOTTOM OF AREA ESTIMATED, HAS NOT BEEN SURVEYED)

-  >50% SURFACE COVERAGE
-  <50% SURFACE COVERAGE
-  TRACE



Jeff DeHonne
4380


DRAFT

SCALE 0 20 40 FEET

NL/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO. 89MC114V
Woodward-Clyde Consultants		
DATE: BY: 7/14/92 DISC: BY: CP CHUB: BY: CIP	REMOTE FILL AREAS: #108 CARVER ST. (EAGLE PARK ACRES)	FIG. NO. 12




⊗ = High Volume pump Locations

High Volume Pump S/N #1- 3118
2- 2964
3- 2292



LEGEND

SURFACE LOCATIONS OF BATTERY CASING MATERIAL
(EXTENT OF AREA ESTIMATED HAS NOT BEEN SURVEYED)

-  >50% SURFACE COVERAGE
-  <50% SURFACE COVERAGE
-  TRACE

Back Ground - 2.42
Predetermined Avg - .14
Action Level 2.56
for Today

Jeff Delhomme
4380

DRAFT

0 20 40
SCALE FEET

NL/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO 89MC114V
Woodward-Clyde Consultants		
DATE BY: CYP 7/14/92 DESIGN BY: CYP CHECK BY: CYP	REMOTE FILL AREAS: 108 CARVER ST (EAGLE PARK ACRES)	PG. NO 12

⊗ = Minivan Location for site Activities

Minivan #1 - 4428


2 - 5427

June 12, 1993

High Volume Pump Locations

Wind E

Temp 88 Hum 42



Back Ground 2.95
Predetermined Ave .035
2.985

Wind E
(0730-130)

COMMENTS: NO BATTERY CASING MATERIAL
PRESENT ON SURFACE

0 30 60
SCALE FEET

ML/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO 89MC114V
Woodward-Clyde Consultants		
DATE BY: CU 7/14/92 DESIGN BY: CHECK BY:	REMOTE FILL AREAS: 203/205 HARRISON ST. (EAGLE PARK ACRES)	PAGE NO 15


DRAFT

(X) High Vol Pump Locations

High Vol Pump #1 3296
#2 3295

File name: C:\GRANITE\HARRISON.DWG Last edited: 92/09/11 @ 14:48

June 12, 1993 Mini Ram Locations for Site Activities Wind E Temp 88 Hum 42%



Wind Direct E
(0730-1130)

COMMENTS: NO BATTERY CASING MATERIAL
PRESENT ON SURFACE

0 30 60
SCALE FEET

ML/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO 89MC114V
Woodward-Clyde Consultants		
DATE: 7/14/92 BY: [signature] CHECKED BY: [signature]	REMOTE FILL AREAS: 203/205 HARRISON ST. (EAGLE PARK ACRES)	PAGE NO 15




DRAFT

Mini Ram Locations
Mini Ram S/N# 5397
#25428

JUNE 5, 1993 Miniram Locations for Site Activities Wind: (NW) Temp: 80° Hum: 17%

LEGEND

SURFACE LOCATIONS OF BATTERY CASING MATERIAL
(PORTION OF AREA ESTIMATED HAS NOT BEEN SURVEYED)

-  >50% SURFACE COVERAGE
-  <50% SURFACE COVERAGE
-  TRACE

COMMENT: TALL GRASS AND UNDERBRUSH OVER MAJORITY OF PARCEL.

All Miniram reading for today are below action level.

Jeff DeHonne
4386

0 20 40
SCALE FEET


ML/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO 89MC114V
Woodward-Clyde Consultants		
DATE BY: CU 7/14/92 DESIGN BY: CHECK BY:	REMOTE FILL AREAS: 100-201 HILL ST. (EAGLE PARK ACRES)	FIG NO 16

DRAFT

⊗ = Miniram Location


Miniram S/N # 1-4703
4583

File name: C:\GRAND\1\HILL 201.DWG last edited: 92/09/11 @ 14:54



File name: G:\CHARLIE\TERRY208.DWG Last edited: 92/09/11 @ 14:57

Nov 23/1993. MinirAM Locations for Site Activities Wind: SE Temp: 93° Hum: 40%




Back Ground: .90
Predetermined Avg: .09
Action Level .99
for Today

Jeff Delhamme
4380

COMMENTS:

1. SURFICIAL TRACE OF BATTERY CASING MATERIAL COVERING WHOLE PARCEL.
2. TALL GRASS AND UNDERBRUSH OVER MAJORITY OF PARCEL.
3. NO FILL MATERIAL OBSERVED.



21-2-17-36-12-203-554

1-800-248-2550
616 656-5744

PAVED
2.1000-1.4000

NL/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO 89MC114V
Woodward-Clyde Consultants		
DATE BY: CU 7/14/92	REMOTE FILL AREAS 208 TERRY ST (EAGLE PARK ACRES)	FILE NO 18

DRAFT

⊗ = MinirAM Location for Site Activities


MinirAM s/n: 1) 4428

2) 5427

3) 4583

File name: G:\GRANITE\TERRY208.LWG Lot edited: 92/09/11 @ 14:37

June 18, 1993 High Volume Pump Locations Wind: SE Temp: 93° Hum: 40%



Jeff Delhomme
4380

COMMENTS:

1. SURFICIAL TRACE OF BATTERY CASING MATERIAL COVERING WHOLE PARCEL.
2. TALL GRASS AND UNDERBRUSH OVER MAJORITY OF PARCEL.
3. NO FILL MATERIAL OBSERVED.

0 20 40
SCALE FEET

NL/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO. B9MC114V
Woodward-Clyde Consultants		
DATE BY CU 7/14/92	REMOTE FILL AREAS 208 TERRY ST. (EAGLE PARK ACRES)	1:1
DESIGN BY		1:1
CHECK BY		1:1

DRAFT

21-2-17-36-12-202-004
1-800-248-2550
615 656-5744

⊗ = High Volume Pump Location

High Volume Pump s/p: 1) 3118

2) 2489

3) 2142


June 14, 1993

Mini Ram Locations At Site Activities

Wind W

Tem 93

Hum 17



LEGEND

SURFACE LOCATIONS OF BATTERY CASING AND SLAG MATERIAL
(EXTENT OF AREA ESTIMATED, HAS NOT BEEN SURVEYED)

>50% SURFACE COVERAGE

<50% SURFACE COVERAGE

TRACE


HAND AUGER BORING LOCATION

DRILLING RIG BORING LOCATION

Back Ground 2.68
Predetermined Avg -13
Action Level 2.81
for today

Zach Moss
5469

COMMENTS:
RESIDENT INDICATED THAT LAND
NORTH OF DASHED LINE IS LEASED
RR PROPERTY



ML/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO 89MC114V
Woodward-Clyde Consultants		
DRN BY: CU 7/14/82 JSDH BY: CHIB BY:	REMOTE FILL AREAS: MISSOURI AVENUE	FIG. NO. 20


DRAFT

Mini Ram Locations
mini Ram test 3/N #1 5397
#2 5428
#3 11278

JUNE 16, 1993 Mini Ram / STIONS

LEGEND

SURFACE LOCATIONS OF BATTERY CASING MATERIAL
(EXTENT OF AREA ESTIMATED HAS NOT BEEN SURVEYED)



Background .00 mg/m^3
Pre AUG - .10 mg/m^3

Action Level .10 mg/m^3

Mark Smolan
1817


0 20 40
SCALE FEET

NL/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO 89MC114V
Woodward-Clyde Consultants <small>Engineering & sciences united to the world & the environment</small>		
DRN BY: CU 7/14/92 DSGN BY: CHWD BY:	REMOTE FILL AREAS: 2230 CLEVELAND	FILE NO 23

DRAFT


⊙ = Mini Ram Location

Mini Ram s/n #
1 - 3296
2 - 3295
3 - 2534



File name: C:\GRANITE CLEVELAND.DWG Last edited: 92/09/16 @ 15:53

~~1993~~ 1993 Hill 1/4 = 400' x 600'





LEGEND

SURFACE LOCATIONS OF BATTERY CASING MATERIAL
(EXTENT OF AREA ESTIMATED HAS NOT BEEN SURVEYED)

- >50% SURFACE COVERAGE
- <50% SURFACE COVERAGE
- TRACE

WIND DIRECTION
(1200-1600)

Mark Adams
1817



⊗ = High Vol. pump locations


DRAFT

NL/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO. 89MC114V
Woodward-Clyde Consultants		
DATE: 7/14/92	REMOTE FILL AREAS: 2230 CLEVELAND	IN. NO. 23

92-93




Mini Ram Locations

Temp 92 Wind SE Hum 40%



LEGEND

SURFACE LOCATIONS OF BATTERY CASING MATERIAL
(EXTENT OF AREA ESTIMATED HAS NOT BEEN SURVEYED)

-  >50% SURFACE COVERAGE
-  <50% SURFACE COVERAGE
-  TRACE

Background $.07 \text{ mg/m}^3$

Pre Avg 1.7 mg/m^3

Action Level 1.8 mg/m^3

Mark Simon
1817

0 20 40
SCALE FEET

Ⓚ = Mini Ram Location

DRAFT

NL/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO 89MC114V
Woodward-Clyde Consultants		
DATE BY CU 7/14/92 DESIGN BY CHECKED BY	ADDITIONAL REMOTE FILL AREAS 1628 DELMAR	SCALE 24

Mini Ram S/N #1 5799
#2 5797




6-23-93


High Volume Pump Locations

Temp 92 Wind SE Hum 40%

LEGEND


SURFACE LOCATIONS OF BATTERY CASING MATERIAL
(EXTENT OF AREA ESTIMATED HAS NOT BEEN SURVEYED)

-  >50% SURFACE COVERAGE
-  <50% SURFACE COVERAGE
-  TRACE



Wind Directional
(0700 - 1600)

Mark Skuman
1817



⊗ = High Volume Pump Locations

DRAFT


pump S/N # 1 - 3296

NL/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO. 89MC114V
Woodward-Clyde Consultants <small>Engineering & Science Center for the City of St. Louis</small>		
DRN BY CU 7/14/92 DESGN BY CHECK BY	ADDITIONAL REMOTE FILL AREAS. 1628 DELMAR	SCALE 1" = 40' 24

JUNE 15, 1993 Mini Ram Locations for Site Activities WIND: NE Temp: 83° Hum: 90%

LEGEND

SURFACE LOCATIONS OF BATTERY CASING MATERIAL
(OUTLINE OF AREA ESTIMATED HAS NOT BEEN SURVEYED)



Back Ground - .00 mg/m³
Pre determined Avg - .51 mg/m³
Action Level - .51 mg/m³

Mark Sabman
8/17

0 20 40
SCALE FEET

ML/TARACORP SUPERFUND SITE
GRANITE CITY, ILLINOIS
PRE-DESIGN FIELD INVESTIGATION

PROJECT NO.
89MC114V

Woodward-Clyde
Consultants

Engineering & scientific services to the earth & the environment

DRAWN BY: CU 7/14/92
DESIGN BY:
CHECKED BY:

ADDITIONAL
REMOTE FILL AREAS:
3108 COLGATE

FILE NO.
25

DRAFT

⊗ = Mini Ram locations

Mini Ram S/N: #1 - 5317
#2 - 5428
#3 - 4378


File name: C:\GRANITE\COLGATE.DWG Last edited: 92/09/11 @ 14:58

June 13 1993 Aest. Palm Pump Locations Wind: NE Temp 13 - Hum 40%

LEGEND

SURFACE LOCATIONS OF BATTERY CASING MATERIAL
(EXTENT OF AREA ESTIMATED HAS NOT BEEN SURVEYED)

- >50% SURFACE COVERAGE
- <50% SURFACE COVERAGE
- TRACE



Handwritten signature and date 18/7

0 20 40
SCALE FEET



③ = High Volume Pump Location

DRAFT

pump SN = 1st 3296
2nd 3295
3rd 2534

NL/TARACORP SUPERFUND SITE GRANITE CITY, ILLINOIS PRE-DESIGN FIELD INVESTIGATION		PROJECT NO. B9MC114V
Woodward-Clyde Consultants		
DRN BY: CU 7/14/92 OSCH BY: CHLD BY:	ADDITIONAL REMOTE FILL AREAS: 3108 COLGATE	FIG. NO. 25